BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the work:-Provisioning Rain water harwesting units in ward no.8 Kodigehalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	144.13	Earthwork excavation in soil, clay ,sand, shedu soil,soft murrum, including shoring , strutting barricading, danger lighting, bailing out water wherever necessary with stacking the materials as directed upto a lead of 50mtr and lift of 1.5 mtr etc., complete.	cum	148.32	Rupees One Hundred Forty Eight and Thirty Two Paise Only
2	48.04	Add for additional lift charges for every lift of 1.5 mtr. Or part there of up to 10.50 mtr	cum	24.72	Rupees Twenty Four and Seventy Two
3	315.00	Supplying and erection of RCC rings for well steining of 0.3m depth using M-20 grade cement concrete using clean graded granite or trap of jelly of approved quality 20mm and down size well compacted including centering form work and plastering for both faces with C M 1:3 porportion as per design 6.50mm M.S. Coil at the rate of 10 kgs/ring including cost of steel and fabrication bailind out of water errection etc ii) For 1.50mtr dia (clear) rings of steining thcikness 0.075mtr upto 18 M depth.	Each	1396.68	Rupees One Thousand Three Hundred Ninety Six and Sixty Eight Paise Only
4	17.58	40 mm nominal size	cum	825.00	Rupees Eight
5	39.56	20 mm nominal size	cum	1050.00	Rupees One
6	39.56	12.5mm nominal Size	cum	950.00	Rupees Nine Hundred
7	39.56	Pea size gravel/6mm and down stone gri	cum	350.00	Rupees Three
8	138.51	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	cum	83.16	Rupees Eighty Three and Sixteen Paise Only
9	29.97	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement 220kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @o.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications	cum	5236.92	Rupees Five Thousand Two Hundred Thirty Six and Ninety Two Paise Only
10	70.20	Providing and constructing precast concrete soild blocks with compressive strength not less thatn 3.5 newton per sqmm with cement mortar 1:4 masonry (Quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to IS 2185/1965 in superstructure including cost of materilas, labour charges scaffolding curing complete as per specifications	sqm	1018.44	Rupees One Thousand Eighteen and Forty Four Paise Only
11	6.48	Providing and laying in position plain cement concret of mix 1:2:4 with cement @ 240kgs with 20mm and down size graded granite metal coarse agregates @ 0.69cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exeeding 15 cm thick well compacted in foundation and plinth and cills, including cost all materilas, labour, HOM of machinery, curing complete as per specifications	cum	5490.72	Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only

No of corrections - Nil

30/12

E.E. (BTP. DIV)

30/12

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
12	1500.00	Providing and fixing Precast soild cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165mm respectively, 400mm hight and 450mm in length finished with CM 1:3 plastering and finishing cutting , including form work, curing, including cost of all materials, labour hire charges of machinery, loading, unloading lead and lift transportetion etc complete	Nos	320.76	Rupees Three Hundred Twenty and Seventy Six Paise Only
13	303.75	Painting two coats on new concrete surface painting two coats after filling the surface with synthetic enemel paint in all shades on new plastered concrete surface complete as per specifications	sqm	68.04	Rupees Sixty Eight and Four Paise Only
14	314.00	Lead for disposal of debris shall be payable at carrage rates by mechanical means including loading and unloading From 13.30 Kms	cum	123.20	Rupees One Hundred Twenty Three and Twenty Paise Only

No of corrections - Nil

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

30/12

30/12

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಯ ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಬದ್ಧಪಡಿಸಿಲ್ಲ ಹಂಬೈ..... (Nil)
ಬದ್ಧಪಡಿ ~~ಸಿದಿ~~/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

06.01.17